

# DOUBLE RING SPANNER




**RED LINE**


**Version: metric, deep offset**

- Drive: Double hexagon
- Standard: DIN 838/ DIN 475-2
- Material: chrome-vanadium-steel
- Surface: Chrome matt plated

Minimized outside dimensions, clear, rounded contours and smoothed edges characterize the narrow design.



Screw connections on deep-seated screws can be optimally undone thanks to the deep offset ring heads.



| mm      | L mm | a1 mm | a2 mm | dia. d1 mm | dia. d2 mm | h mm | Art.                | P. Qty. |
|---------|------|-------|-------|------------|------------|------|---------------------|---------|
| 6 × 7   | 175  | 5     | 5.8   | 10.5       | 11.4       | 19   | <b>5754 305 067</b> | 1/50    |
| 8 × 9   | 185  | 6     | 7     | 13.4       | 14.8       | 21   | <b>5754 305 089</b> |         |
| 8 × 10  | 185  | 6     | 7     | 13.4       | 14.8       | 22   | <b>5754 305 080</b> |         |
| 10 × 11 | 198  | 7.4   | 8.4   | 16.4       | 17.9       | 23   | <b>5754 305 101</b> |         |
| 12 × 13 | 215  | 8.4   | 9.1   | 19.5       | 20.6       | 25   | <b>5754 305 123</b> |         |
| 13 × 17 | 245  | 10    | 10.8  | 20.9       | 26.2       | 27   | <b>5754 305 137</b> | 1/25    |
| 14 × 15 | 228  | 9.5   | 10.4  | 22.2       | 23         | 25   | <b>5754 305 145</b> |         |
| 16 × 17 | 246  | 10    | 10.8  | 24.5       | 26         | 27   | <b>5754 305 167</b> |         |
| 16 × 18 | 246  | 10    | 10.8  | 24.5       | 26         | 28   | <b>5754 305 168</b> |         |
| 17 × 19 | 268  | 10.8  | 12.1  | 26.4       | 28.4       | 30   | <b>5754 305 179</b> |         |
| 18 × 19 | 268  | 10.8  | 12.1  | 27.5       | 28.4       | 30   | <b>5754 305 189</b> | 1/15    |
| 20 × 22 | 292  | 11.7  | 12.5  | 30.7       | 33.5       | 31   | <b>5754 305 202</b> |         |
| 21 × 23 | 315  | 12.2  | 13.2  | 31.8       | 34.8       | 32   | <b>5754 305 213</b> |         |
| 22 × 24 | 315  | 12.2  | 13.2  | 31.8       | 34.8       | 32   | <b>5754 305 224</b> | 1/10    |
| 24 × 26 | 328  | 12.2  | 13.4  | 36.3       | 39.6       | 36   | <b>5754 305 246</b> |         |
| 24 × 27 | 328  | 12.2  | 13.4  | 36.3       | 39.9       | 36   | <b>5754 305 247</b> |         |
| 25 × 28 | 342  | 13.9  | 14.9  | 37.4       | 41.4       | 35   | <b>5754 305 258</b> |         |
| 27 × 29 | 365  | 14    | 15.8  | 39.9       | 46.3       | 36   | <b>5754 305 279</b> |         |
| 30 × 32 | 370  | 15.2  | 16    | 43.5       | 46.3       | 36   | <b>5754 305 302</b> | 1/5     |
| 36 × 41 | 445  | 17.3  | 18.3  | 52.7       | 60.2       | 42   | <b>5754 305 361</b> |         |

| Set    | mm   | Art.               | P. Qty. |
|--------|--|--------------------|---------|
| 12 pcs | 6 × 7, 8 × 9, 10 × 11, 12 × 13, 14 × 15, 16 × 17, 18 × 19, 20 × 22, 21 × 23, 24 × 27, 25 × 28, 30 × 32 | <b>5754 305 42</b> | 1       |

